



Leakage control station

for flange mounting

Mechanical engineering	Realizations	Cabling	O Machines
• Meenanieat engineering	- NCGGZGGIS	Cabing	U Macmines

This station, **entirely pneumatically driven**, allows the **normative control** of a flange assembly for pressurised elements.

The operator safety is cleverly ensured by a ¼ turn flange which keeps the part to be tested trapped in case of failure.


After inflation, the operator sprays the part with soapy water.

At the same time, the unclamping movement controls the purging of the chamber.

SPECIFICATIONS:

- Pneumatic power only
- Adjustable pressure from 0 to 6 bar
- · Active part in stainless steel







Reference: 3611
Project added the 27/09/21





